



NATIONAL AUTOMOTIVE TESTING AND R&D INFRASTRUCTURE PROJECT

(A Registered Society under Ministry of Heavy Industry and Public Enterprises)

Ref. No. 58/NATRIP/GARC/2019-2020/232- NIQ

Date: 09th August 2019

NOTICE INVITING QUOTATION (NIQ)

Subject: Construction of UG Sump with Pump and Pipe Line Works at PWT Pump House at NATRIP – Global Automotive Research Centre (GARC), Plot E1, SIPCOT Industrial Growth Centre, Oragadam, Mathur Post, Sriperumputhur Taluk, Kanchipuram Dist – 602 105.

Dear Sir,

National Automotive Testing and Research & Development Infrastructure Project (NATRIP) Implementation Society under Government of India, Ministry of Heavy Industries & Public Enterprises invites quotations from registered and authorized firms for “for **Construction of UG Sump with Pump and Pipe Line Works at PWT Pump House at**” at ‘Global Automotive Research Centre (GARC) at Plot E-1, Oragadam Industrial Growth Centre Oragadam, Mathur Post, Sriperumbadur, and Taluk Kanchipuram District-602105.

2. The sealed bids titled “Quotation “With ref no of the document addressed to the “**Procurement Officer**” **Global Automotive Research Centre (GARC), Plot E1, SIPCOT Industrial Growth Centre, Oragadam, Mathur Post, Kanchipuram Dist-601 105, Tamil Nadu, INDIA**” shall reach by 26th August 2019 @ 3.30 pm.

3. BOQ & Detailed Requirements as per annexure 1

4. Terms & Conditions:

1. The rates shall include all costs against mobilization and demobilization of your equipment and professional personnel, unskilled labors, necessary arrangement like site clearing, lights, power supply etc., GARC will not arrange any security for your equipment.
2. The offer shall include any other activity related to the scope of the work as in title above needed for the project but not explicitly mentioned above.
3. It shall be the responsibility of the successful bidder to complete the job as per the technical specifications stated herein in at Global Automotive Research Centre (GARC).
4. The rates quoted by the bidder shall remain firm till the completion of the job/work order and price variation shall not be entertained.
5. The prices should be quoted must be free from any kind of overwriting, alteration and correction.
6. Taxes/GST, if any should be mentioned separately.
7. The agency shall carryout the work within 45 days (Forty Five days) against the acceptance of the work/purchase order.
8. Prospective bidders may visit the premises to ascertain the scope of works involved, before submitting their quotation.



NATIONAL AUTOMOTIVE TESTING AND R&D INFRASTRUCTURE PROJECT

(A Registered Society under Ministry of Heavy Industry and Public Enterprises)

Ref. No. 58/NATRIP/GARC/2019-2020/232- NIQ

Date: 09th August 2019

9. It shall be ensured by your agency that all your equipment is handled carefully while doing works without causing any damage to GARC premises.
10. Cost of any damages shall be recovered from agency.
11. It shall be your agency's liability to avoid any causality during the work in all respects, any kind of causality to be borne by your agency.
12. It shall be your agency's liability to avoid any losses or damages by wrongful act; or negligence; or irresponsibility; or carelessness during the work.
13. The Competent Authority of this office reserves the rights to reject any or all the quotations without assigning any reason and the decision of the competent authority of this office shall be final and binding.

5. Terms of Payment:

1. 100% payment shall be release after supply of items/Works, as certified by engineer incharge of the lab.
2. Payment shall be released within 45 days from the date of submission of work completion report signed by engineer incharge of the lab.
3. At the time of payment of bills, the taxes liable to be deducted, if any, shall be deducted at source as per Government rules and guidelines as may be prevailing at the time of payment
4. All payments to the Vendor shall be made by Account payee cheque or RTGS in Indian Rupees
5. Liquefied Damages: In the event of delay on part of the supplier/contractor to achieve completion of the work within the time lines as specified in the quote, the supplier/contractor liable to pay to GARC a sum equal 0.5% of the contract price for every week of delay, or part thereof, subject to the maximum of 10% of the contract price, for such default as liquified damages, which the supplier/contractor is not a penalty but a genuine pre-estimate of loss and damage likely to be suffered and incurred by GARC for every day, or part thereof, that such delay subsists till the date of actual completion. GARC may, without prejudice to any other method of recovery, deduct the amount of such damages from any monies due or to become due to the supplier/contractor.

GARC shall be at liberty to withhold any of the payments in full or in part subject to recovery of taxes including TDS as applicable


Rajeswar Tripathy
(Procurement Incharge)

ANNEXURE-1						
BOQ for Construction of UG Sump with Pump and Pipe Line Works at PWT Pump House --GARC, Chennai						
SR. NO.	DSR-2018	Description of the Items	Units	Total Quantity	Rate	Amount
1	2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding) 30 cm in depth, 105 in width as well as 10 sqm om plan) including getting out and disposal of excavated earth lead upto 50m and lift upto 1.5m, and levelled neatly as directed by Engineer-in-charge	Cum	43.43		
2	4.1.8	Providing and Laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 cement : 4 coarse sand (Zone-II) : 8 graded stone aggregate 20mm nominal size)	Cum	3.62		
3	5.22.6	Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo - Mechanically Treated bars	Kg	303.81		
4	5.1.2	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level. 1:1.5:3 (1 cement :1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size)	Cum	5.43		
5	5.9.1	Centering and shuttering including strutting, propping etc. and removal of form for foundations, footings, bases of clourms, etc. for mass concrete	Sqm	6.20		
6	6.32.1	Brick work with clay flyash F.P.S (non modular) brick of class designation 705 in superstructure above plinth level up to floor five level in : Cement mortar 1:4 (1 cement: 4 fine sand)	Cum	6.35		
7	13.2.1	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement : 4 fine sand)	Sqm	54.40		
8	NDSR	Supplyign and fixing 10 HP Centrifugal Monoblock pump with necessary inlet and outlet fittings, Starter Panel, Power Cable etc the rate including labour, transport etc	Nos	1.00		
9	NDSR	Supplying and fixing of 50mm HDPE pipe from UG sump to Bore well inlet with necessary fittings	Mtr	70.00		
				TOTAL		
					GST, if any	
					TOTAL AMOUNT	

IN WORDS:

Work Completion Period:



